		ANTS - SCHEDULE	
Note: All amounts exclude Vat @ 13.5%			
Date: Updated: 10th June 2022			
Description	Unit	Cost	Remarks
DOOFING			
ROOFING			
Domovo ovietina eletes/tiles ⁹ dienes	m ²	€25	5 J. P. O. W. P.
Remove existing slates/tiles & dispose	m ²		Excluding Scaffolding.
Replace roof timbers	·	€ 35	Area on plan. 600 x 300mm slate including roof
Felt Batten & Slate	m ²	€58	ventilation products (Fibre cement slate – measured on slope as plan area would depend on roof pitch which varies, junctions, dormers, valleys etc.)
Fascia & soffit	l.m	€40	uPVC.
Provision of Upvc cladding to existing fascia,	l.m	€25	
soffit and barge boards		2	
Rainwater goods	l.m	€18	Upvc Gutters & Downpipes
Replaster chimneys	item	€250	Assume 600 x 600 x 1000mm high chimney
Demolish & rebuild chimney	item	€2,450	Based on single storey to ground level
Chimney Flashing	item	€275	Assume 600 x 600 x 1000mm high chimney
Over barge	item	9	Not sure what this is referring to?
Under barge	item	(20	Not sure what this is referring to? Removal not included for
Reslab existing ceiling and skim.	m ²	€30	
Ceiling complete. Install flat roof (to include torch on felt and	m ²	€85 €90	Included for standard joists, slab & skim with plywood on top. No Insulation. Flashing excluded depends on roc
associated flashing)	m²		area size and no of junctions with adjoining walls
Ceiling insulation	m ²	€25	400mm thick or equivalent Mineral Wool.
M/_II _			
Walls			
		0.00	
Completion of Dividing wall in attic space petween two houses	m²	€100	100mm concrete block on flat not plastered
Fire Compartmentation Works to Party Wall at Roof.	l.m	€50	
Insulate outer walls and skim	m²	€50	62.5mm thick
Cavity Wall Insulation	m ²	€18.50	Pumped Bead Insulation - 100mm Cavity. Gables
		611/	additional
Paint per room	m²	€11/m2	Per m2 room size varies
Paint Externally	item	€17/m2	incl power wash with fungicide. Priced per m2 as house sizes can vary.
Paint Woodwork - Single Door	No	€150	including door, frame & Architrave.
Painting Woodwork n/e 300mm wide	l.m	€8	Skirting/window boards.
Skirting boards	l.m	€8	
Wall Tiles	m ²	€65	
Windows and Doors			***************************************
Windows supply and fit - Large	no.	€950	Upvc Double Glazed - U Value of 1.1 w/m²k.
Windows Supply and Fit - Small	no.	€450	Upvc Double Glazed - U Value of 1.1 w/m²k.
External Single doors Supply and fit	no.	€1,100	Upvc Door.
Internal Single doors supply and fit	no.	€450	Non Fire Rated including Ironmongery & architrave
Internal Single doors supply and fit	no.	€500	FD30 including Ironmongery & architrave
Patio door	no.	€2,750	incl breakout
Floors			
Dig out and replace.	m²	€165	incl radon & insulation.
Non slip tiles supply and fit.	m²	€65	
Radon Remediation.	item	€1,250	Scope of remediation? Provisional allowance
Laminated floor.	m ²	€25	
Access		C2 000	
Construct ramp to front door including rail.	l.m	€2,000	0. 1
Stair lift. Handrails with brackets S&F.		€2,350 €180/m	Straight stairs with manual swivel (assume plug nearby) Mild Steel, painted fixed to wall.

MAYO CO CO	HOUSIN	NG GRANTS - SCHED	OULE OF WORKS
Note: All amounts exclude Vat @ 13.5%		- GIANTO - GOTTLE	
Date: Updated: 10th June 2022	I India	0.	Demonto.
Description	Unit		ost Remarks
Description	Unit	Co	ost Remarks
Extensions			
Demolition and removal from site of existing buildings.	item	€110/m2	Allowance included per m2 demolition depends of size of building
Bathroom Extension.	m ²	€3,000	
Bedroom Extension.	m ²	€2,500	
Bathroom			
Remove bath & fit shower complete	item	€1,550	Including Tiling & Shower Curtain.
Level deck shower only to include new electric shower unit		€1,350	
Electric shower unit only supply and fit	item	€550	
Sink and taps S&F	item	€325	
W.C & cistern	item	€290	
Curtain Rail s&f / half height door	item	€350	
Extraction Fan	item	€450	Incl forming ope and wiring
Grab rail Fixed (at toilet)	item	€50	
Grab rail Adjustable (at toilet)	item	€150	
Water Services			
Water connection fee		€2,272	Up to 10 meters
Lay Water Mains	l.m	€40	
internal Plumbing		€4,000	incl header tank cylinder
Waste Water Connection Fee		€3,929	Up to 10 meters
WWTP	'a	€3,000	Tricel P6 or equivalent
Manhole Sewer Line Pipework.	item	€1250 €40	Standard Manhole 500 - 1000mm deep.
Sewer Line Pipework.	l.m	640	
Heating			
Condensing oil boiler	item	€3,500	97% Efficiency Rating.
Oil Tank	item	€1,500	Incl Bund and Tiger Loop System.
Indirect Cylinder	item	€950	
Immersion Time switch	item	€275	
Radiator	item	€320	Incl TRV and rebalancing of system.
Header Tank	item	€350	
Circulation Pump Solar Panels	item	€200 €3,000	
Back Boiler		€1,500	
Range	item	€4,500	PC Allowance (Spec, size solid fuel/ oil etc?)
Multi Fuel Stove with Boiler - Supply & Fit	item	€2,850	PC Allowance (Spec, size etc?)
Multi Fuel Stove - Supply & Fit	item	€2,450	Incl Hearth and Fresh Air Intake. PC Allowance (Specsize etc?)
Storage Heater	item	€500	22000
Electrical			
Rewire Completely - 800 sq/f dwelling	item	€8,500	Include for New Fuse Board, Smoke Alarms, Carbon Monoxide Alarm, Doorbell and re wiring.
Rewire Completely - 1,100 sq/f dwelling	item	€11,000	
Carbon Monoxide Alarm S& F	item	€200	Per Single Unit
Smoke Alarms S&F	item	€150	Per Single Unit
Individual power points	item	€120	Per Single Unit